Railways

App F IX 4

Previous References 1928 (nil)

File No 69 28

Serial Nos. 50255

Later References
W. 3-33, 163 168

General and Revenue Secretariat.

Serial Nos

Part B for May 29

SUBJECT

Estimate for laying sewerage pipe line in Chammundi extension Sanctioned by the Board of Trustees

55 To, The Chairman of Bd Mysore
Re Completion to Cover
No L 7685-6/L 22 & 29
Sanctions the estimate
referred to above

Ml 69-28-50

No 1342 / 2 5 29

Enc plans in duplicate
Estimate in duplicate
Report
Board Resolution

OFFICE OF THE CHAIRMAN
CITY IMPROVEMENT TRUST BOARD MYSORE

Dated 1st May 1929

GEN & F V SECTT
L4856
7 MAY 1929
L S G BRANCH

FROM

Y Ramaswami Esquire, B A C E
~~Y RAMASWAMI IYER ESQ B A~~
Chairman City Improvement Trust Board
Mysore

OFFICE OF THE SEC M CO N IL
17 MAY 1929
No 8941

TO

The General Secretary to the Government of
His Highness the Maharaja of Mysore
Bangalore

SIR

I have the honour to forward herewith an estimate for laying severage pipe line in Chamundi Extension sanctioned by the Board of Trustees at their Ordinary meeting held on the 23rd March 1929 and to request that you may be so good as to obtain the sanction of Government thereto

The report accompanying the estimate and plans in duplicate explains the nature and necessity for the work

A copy of the Board's Resolution thereon is also forwarded for reference

The cost of the estimate is R 8 835 and the excess over the budget provision of Rs 5 000 will be met by re-appropriation of budget grants for the year

I have the honour to be

Sir

Your most obedient servant

Y Ramaswami
Chairman

Subject to draft being approved
A sum of Rs 5000/- is included in the budget for 1928-29 for the item of work

15/5/29

REV SECTT
3 MAY 1929
No L7685-6 & 22 5 29

Second Member
Chairman, Trust Bd
Comp

16/5-

15/5-29

Proceedings of the 9th Ordinary meeting of the Board of Trustees for the Improvement of the City of Mysore held at the Chairman's Office on Saturday the 23rd March 1929 at 8 A M.

Present

T G Rama Iyer Esquire B A (Chairman)

1 The Sanitary Commissioner of Mysore
2 The Vice President Mysore City Municipal Council
3 The Health Officer Mysore City Municipal Council
4 Rajakaryaprasakta D K Darasha Esquire B A
5 J E A D'Cruz Esquire A C E B C E

Absent

1 Sir Charles Todhunter K C S I
2 Mahomed Sait Esquire
3 K Dhanakotichetty Esquire

---

x x x x x x

XXXII Estimate for Rs 8 835 for laying severage pipe line in Charundi Extension

Sanctioned

x x x x x

Sd/- T G Rama Iver
Chairman

" C O P Y "

G Ranchem
Chairman

(3

Report to accompany the estimate for laying sewage pipe line in Chamundi Extension

---

The lines that are proposed to be laid have been found necessary as the sevage of the houses have been logging up in the streets and the people are frequently complaining Lost of the lines on the northern side have been completed The lines are being laid year by year as the houses spring up This is one of the budgetted items during the year for which a provision of Rs 5 000 is made in the current year's budget As the lines canrot be taken up by piece-meal sanction may kirdly be taken for the estirated amount and the balance amount can be met out of the general savings

The proposal is to lay 7" line to a length of 2 353 Running feet and to construct 13 ranholes and to give 45 house connections at a total cost of R 8 835

Sanction may kindly be accorded to the estimate

M Ramaswamy
Chairman

2/

4

MYSORE CITY IMPROVEMENT TRUST BOARD

Estimate for the probable cost of Laying stretch sewer from pipe line in Chamundy Extension Mysore

W D 249—GBPM—500—28 8 28

Particulars of work	No	Dimensio			Cont nts	Total	Unit	Rate			Amount		
		l	B	D				Rs	a	p	Rs	a	p
Laying stretch sewers													
with work excavation and refilling													
Man hole No 1 to 12	1	167	2½	$4\frac{50+606}{2}$	2204								
" 12 to 33	1	167	2½	$6\frac{06+624}{2}$	2568								
1 to 2	1	145	2½	$4\frac{50+533}{2}$	1782								
" 2 to 3	1	145	2½	$5\frac{33+434}{2}$	1753								
" 3 to 31	1	58	2½	$4\frac{34+639}{2}$	778								
" 4 to 4	1	216	2½	$5\frac{21+669}{2}$	3213								
" 4 to 5	1	217	2½	$6\frac{69+769}{2}$	3901								
" 5 to 6	1	217	2½	$7\frac{69+739}{2}$	4090								
6 to 7	1	172	2½	$7\frac{39+653}{2}$	2993								
" " 7 to 8	1	172	2½	$6\frac{53+988}{2}$	2668								
8 to 9	1	172	2½	$5\frac{88+400}{2}$	2124								
9 to 10	1	253	2½	$4\frac{00+568}{2}$	3086								
10 to 11	1	150	2½	$5\frac{68+500}{2}$	2002								
" 11 to 20 Existing M H	1	100	2½	$5\frac{00+500}{2}$	1250								
Total in ofs					34412	1275 cft							
Ordinary soil					~~426~~	426 cft			6		159		
Soft rock						425			8		212		
Hard rock						425		2			810		
2d of glazed 7 S W Pipes	1	2233			2233	2233	Rft	1	2	6	2582		
of 7×4 Rectangular Metre:	1	120			120	120	Rft	2	8		300		
ing laying & fitting 7 S W Pipes	1	2353			2352	2353	Rft		2	9	404		

Carried over

Brought forward									
Constructing Square Man holes	7	-	-	7	7	Each	150		1050
Constructing Circle Man holes	6			6	6	"	140		840
Constructing House connections	45		-	45	45	"	35		1575
Constructing Ventilating Shafts	2	-	-	2	2	"	200		400
Carting surplus earth	1	1275/6	-	212	212	938	"	3	40
Total									8412
Contingencies at 5 %									423
Grand Total Rupees									8835

Trust Bond Engineer

A Ramsbotham
Chairman

Hazaree bagh 2

Discharge statement for laying sewerage pipe

Drawing station	Block No	Main Submain or street sew	Pmh or sewer	Length of section in feet	Ground Level	Invert Level	Depth of cutting	Size of pipe	Gradient 1 in	Velocity	Square manhole
Chamundy Layout	Extension	Sheech sewer	9	0	2423 63	2419 03	4 60	↑	↑		1
			12	167	2421 82	2415 76	6 06	7	51	3 99	
			32	167	2418 68	2412 44	6 24	↓	↓		(1)
			1	0	2420 80	2416 30	4 50	↑	↑		1
			2	145	2419 70	2414 37	5 33				
			3	145	2416 78	2412 44	4 34	7	75	3 29	1
			31	58	2418 06	2411 67 / 2409 77	6 39 / 8 29	↓	↓		
			A	0	2411 46	2406 25	5 21	↑	↑		(1)
			4	216	2410 78	2404 09	6 69				
			5	217	2409 61	2401 92	7 69	7"	100	2 85	
			6	217	2407 14	2399 75	7 39	✱	✱		1
			7	172	2403 66	2397 02	6 53				
			8	172	2400 17	2394 29	5 88	7	63	3 59	
			9	172	2395 63	2391 63	4 00	×	×		1
			10	255	2389 51	2383 83	5 68	7 ×	33 ×	4 97	1
			11	150	2306 144	2381 44	5 00	7 ×	63 ×	3 59	1
			20	100	2383 39	2378 39 / 2376 40	5 00 / 6 99	7 ↓	32 ↓	5 04	(1)

...ench Trunk Road

...n Chamundy Extensions

Circular Man hole	Tank Catching Shaft	House Connection	Remarks
		1	Existing man hole
	1		
①			Drop 1.90 Existing Man hole
	1		Existing man hole
		45	
		2	1.99 Drop Existing man hole

Board Engineer

Chairman

—Mysore City Improvement—

—Trust Board—

Duplicate

Estimate for laying sewerage pipe line in Chamundy Extension

9

G R S VI G 34]

SUBJECT

Diary No of letter replied to 4856

General and Revenue Secretariat

( )

the *192*

Date of issue 22 5 1929

Signed by Mr D R S Iyer

May this be

i Printed ?

ii treated as a standing order ?

iii published in the Gazette
English Part ?

iv translated ?

v placed at the disposal of the press ? P & D

vi published in the Gazette
Kannada Part ?

Section MP
File No 69-28
Serial No 55

Proceedings of the Government of
His Highness the Maharaja of Mysore

Read— 1 G O No 4034-39-FE 306-27-49 dated the 23rd June 1928 sanctioning the Budget Estimates of the Mysore City Improvement Trust Board for the year 1928-29 and providing a sum of Rs 5000/- for laying the pipe line in the Chamundi Extension at Mysore

Order Thereon No

2- Letter no 1342 dated the 2nd May 1929, from the Chairman, City Impt Trust Board Mysore Solicitors, under the circumstances explained, sanctioning to

the Board's Resolution
dated 23rd March 1929
approving an
estimate for Rs 8,835/=
for laying the pipe line
in Chamundi Extension
Mysore the excess of Rs 3835/=
over the sum
Rs 5,000/= provided in
the Budget of the District Board
Board for 1928-29 being
met by re-appropriation
of sanctioned grants
during the current year.

Order No L 7685-6 / Enc Estimate & plan
dated 22nd May 1929

The estimate
is sanctioned
for Rs 8835/= Mr Rees Capt Ivan suggests re-appropriation as shown above

1" Rr
28/15/- Gent Secy to Govt

List of enclosure.

Y&S
10/5/29 N 6145

Copied by

Examined by

To The Chairman City
Improvement Trust Board, Mysore
with the Board's estimate for
Camp Rs [illegible] for the Govt of Mysore

WD 188 —61 B—1 000 00—21 12 2

Exhn

11

Proceedings of the Government of His Highness the Maharaja of Mysore

---

R e a d:-

Government Order No L 9034-39 Ml 306-27-49 dated the 23rd June 1928, sanctioning the Budget Estimates of the Mysore City Improvement Trust Board for the year 1928-29 and providing a sum of Rs 5,000/- for laying the pipe line in the Chamundi Extension at Mysore

2 Letter No 1342 dated the 2nd May 1929, from the Chairman, City Improvement Trust Board, Mysore, soliciting under the circumstances explained, sanction to the Board's resolution dated 23rd March 1929 approving an estimate for Rs 8,835/- for laying the pipe line in Chamundi Extension, Mysore, the excess of Rs 3,835/- over the sum of Rs 5,000/- provided in the Budget of the Trust Board for Rs 1928-29 being met by re-appropriation of --- sanctioned grants during the current year

---

ORDER NO L 4685-6/me69-28 55

Dated, Bangalore the 22nd May 1929

The estimate is sanctioned for Rs 8,835/- the excess cost being reappropriated as suggested above

For General Secretary to Government

To

The Chairman, City Improvement Trust Board, Mysore, with the sanctioned estimate
The Comptroller to the Government of Mysore

K M R 3
21/5